


BRUHAT BANGALORE MAHANAGAR PALIKE**Project Division, Yelahanka Zone****Modified SCHEDULE - B****Name of Work: Improvements to Park beside to Ganesha Temple Sahakara Nagara in Ward no. 08**

SNo	Quantity	Item Name	Unit		
				In figures	In words
1	75.55	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. Specification No. 301. (P.No.143, I.No.19.1 of PW, P&IWD SR 2018-19)	Cum	226.04	Rupees Two Hundred Twenty Six And Paise Four Only
2	31.72	KSRRB M300-53. Construction of embankment with approved material Gravel /Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density. MORTH Specification No. 305. (P.No.147,	Cum	361.00	Rupees Three Hundred Sixty One Only
3	40.71	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2 (P.No.13, I.No.4.3 of PW, P&IWD SR 2018-19)	Cum	5678.40	Rupees Five Thousand Six Hundred Seventy Eight And Paise Forty Only
4	159.16	KSRB 4-1.5 : Providing and laying in position plain cement concrete of Mix M20 with OPC @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.43cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No.4.5 of PW, P&IWD S.R 2018-19)	Cum	6350.00	Rupees Six Thousand Three Hundred Fifty Only
5	173.88	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mix finished with flush pointing using white cement, including cost of materials, including cutting, gridding the edge to half/full round wherever required, labour, curing complete as per specification. (P.No. 112, I.No. 14.62 of PWD SR 2018-19)	Sqm	1470.00	Rupees One Thousand Four Hundred Seventy Only


H.V. Y
Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Executive Engineer
Yelahanka Project Division

6	112.32	KSRB 14.6 : Providing and laying heavy duty cobble stones interlock pavers, using cement and coarse sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM complete as per specifications. Specification No. KBS (P.103/I.14.6) PWD SR 2018-19, 60mm thick	Sqm	1200.00	Rupees One Thousand Two Hundred Only
7	533.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc., complete. (P.No.27, I.No.5.30 of PW, P&I WTD SR 2018-19)	Nos	454.10	Rupees Four Hundred Fifty Four And Paise Ten Only
8	331.02	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8. (P.No.180, I.No.24.1 of PW, P&I WTD SR 2018-19)	Sqm	89.04	Rupees Eighty Nine And Paise Four Only
9	5.00	Providing and fixing polished gray granite slab benches of size 5 ft width of seating slab with bottom slab of 75mm thick width 1.50ft with back rest slab of 50 mm thick with 1.50ft depth, side and slab of 100mm thick 2.50 ft height including bull nosing of all edges including fixing in CC 1:2:4 including loading and unloading as per design, specification and fixing as per the directions of the engineer in charge.	Unit	12000.00	Rupees Twelve Thousand Only
E1	84.96	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not less than 1800 kg/m ³ and having a minimum average compressive strength 4.00 N/mm ² confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing complete as per specifications. KBS No.5.4 (P.No.28, I No. 5.26.1)	Sqm	1070.20	Rupees One Thousand Seventy And Paise Twenty Only
E2	84.21	Providing 18mm thick cement plaster in single coat with cement mortar 1:6 to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (P.No.116, I.No.15.17)	Sqm	272.56	Rupees Two Hundred Seventy Two And Paise Fifty Six Only


 Executive Engineer
 Project Division
 Yelahanka Zone
 BBMP, Bangalore-92

E3	213.10	Fabricating, providing and erecting in position of M.S. Ornamental security Grill Gate without hot dip using 75 x 12mm M S Flat for around frame work with verticals at the centre and horizontal centre support MS Square of 20 x20 mm of different heights as shown in the drawing are to be fixed at 16 cms C/C for square bars of full height and at 8cms C /C for bottom rods providing ornamental C I Designers at the bottom and C I arrows in the middle and top. The entire frame work is to be fixed by means of expansion bolts to the brick pillars with Necessary drilling holes. the work includes providing two coats of enamel painting over one coat of red lead ready mix primer coat etc complete cost of all labour, painting, erection charges using hoist pulleycranes with all lead and lift, loading, transporting and unloading using hoist pulley cranes, scaffolding charges and all other incidental charges required for successful completion for the work as per specification and drawings.	Kgs	146.85	Rupees One Hundred Forty Six And Paise Eighty Five Only
E4	285.60	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator & HOM,including cost of blade,coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications.	m	150.18	Rupees One Hundred Fifty And Paise Eighteen Only
E5	5.00	Providing and fixing ornamental Delhi benches as per design specification and fixing as per the direction of engineer in charge	Unit	8500.00	Rupees Eight Thousand Five Hundred Only
E6	1553.80	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.	Sqm	75.65	Rupees Seventy Five And Paise Sixty Five Only


 Executive Engineer
 Project Division
 Yelahanka Zone
 BBMP, Bangalore-92